BRUHAT BANGLORE MAHANAGARA PALIKE

DASARAHALLI-ZONE
T.DASARAHALLI SUB-DIVISION

Name of Work: Providing Rain water Horvesting Facilities in Bagalagunte Ward No 14

Est Cost: 10.00 Lakhs

Head Of Account - POW

P-Code. 1771

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Providing Rain water Horvesting Facilities in Bagalagunte Ward No 14

Est. Cost Rs 10.00 Lakhs

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 · Excavation for road, drains and similar works · KSRRB 300·1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.143/I.19.1 PW, P & IWTD -SR 2018·19)								
		cum	48	2.50	2 50	2.25	675.00		
							675.00	137.80	93015.00
	Basic rate	130.00							
	Add Area Weightage 6%	7.80							
	Total	137.80							
2	KSRRB M100·6. Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 13.2 mm nominal size including cost of materials, equipments, labour etc. complete. MORTH · 100/ Chapter 1 Page No 136, It No 17.8 PWD SR 2018·19								
		Cum	48	2.50	2.50	1.00	300.00		
							300.00	845.88	253764.00
	Basic Rate	798.00							
	Add Area Weightage 6%	47.88							
	Total	845.88							
3	KSRRB M100·8. Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 40 mm nominal size including cost of materials, equipments, labour etc. complete. MORTH · 100/ Chapter 1 Page No 136, It No 17.10 PWD SR 2018·19								
		Cum	48	2.50	2.50	0.50	150.00		
							150.00	760.02	114003.00
	Basic Rate	717.00							
	Add Area Weightage 6%	43.02							
	Total	760.02							

4	KSRRB M100-7. Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 20 mm nominal size including cost of materials, equipments, labour etc. complete. MORTH - 100/ Chapter 1 Page No 136, It No 17.9 PWD SR 2018-19								
		Cum	48	2.50	2.50	0.50	150.00		
							150.00	851.18	127677.00
	Basic Rate	803.00							
	Add Area Weightage 6%	48.18							
	Total	851.18							
5	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications including cost of all materials, labour, HOM, form works, scaffolding & centering complete as per specifications. MORTH Specification No.1207								
		Cum	48	2.50	2.50	0.25	75.00		
							75.00	2806.88	210516.00
	Basic Rate	2648.00							
	Add Area Weightage 6%	158.88							
	Total	2806.88							
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2018-19							69.80	
				Qty Vide Item No 01			750.00	~~73.99~~	~~55491~~.00
	Loading and Unloading	57.00							52 350.00
	Lead 4 KMs 2x1.28x4	12.80							
		69.80							
	Add Area Weightage ~~6%~~	~~4.19~~							851321.00
	Total	~~73.99~~					Sub Total		~~854466.00~~ ~~42566.24~~ ~~42723.00~~
7	Tender Premium Charge 5%								102~~1~~50.00 ~~3949.38~~ ~~275.00~~
8	GST Charge 12%							Total	1000000.00
9	Miscellaneous and UnforessenCharges								
	Rupees Ten Lakhs Only								

Assistant Engineer
Ward No 14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ಸಂ. EE/DD/AS/1MG/19-20 ದಿನಾಂಕ: 03/07/2020

ರೂ. Rs 10.00 Lakh

Rupees Ten Lakh only

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ಸಂ. EE/DD/TS/49/19-20 ದಿನಾಂಕ: 30/01/19

ರೂ. 10.00 Lakhs/- (Rs Ten Lakhs only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು